외국근로자를 위한 5분 인전미팅



5 Minute Safety Meeting

for the foreign workers

Roller Work

A. Dangers in Roller Work

Accidents with the roller may occur that the worker's body is caught into the rollers rotating in reverse direction.

B. Safety in Roller Work

-For the roller making plastic forming or softening of the rubber, rubber compound or synthetic resin, make sure to install emergency stop devices

Types of Emergency Stop	Location
Hand-controlled Type	Less 1.8m from the bottom
Belly-controlled Type	0.8~1.1m from the bootom
Knee-controlled Type	0.4~0.6m from the bootom

- For the roller through which plywood, paper, textile, metal pieces, etc. are past, be sure to install fence or guide roll.

C. Safety Rules on Roller Work

- Check the operating status of safety device including emergency stop before starting the roller work.
- -The emergency stop devices should be installed at the position for the workers in any place to access easily.
- At the part having a danger of trapped in the roller, be sure to install guide roll or fence.
- When cleaning or inspecting the roller, be sure to stop the machine.

로올러기 작업안전

가.로울러기작업의위험요소

로울러기에의한재해는서로반대방향으로회전하 는로울러에작업자의신체가말려들어발생

나.로울러기 안전작업

-고무,고무화합물 또는 합성수지를 소성 변형시키 거나 연화시키는 로울러기에는 즉시 로울러를 정 지시킬 수 있는 급정지장치가 설치된 것을 사용하 여야한다.

급정지장치의 종류	설치위치
손조작식	밑면에서 1.8m 이내
복부조작식	밑면에서 0.8~1.1m 이내
무릎조작식	밑면에서 0.4~0.6m 이내

-합판,종이,천및금속판등을통과시키는로울러기 에는울또는가이드롤등이설치된것을사용하여 야한다.

다.로울러기 작업 안전수칙

- -로울러기는 급정지장치 등 안전장치의 작동상태 를확인한후작업한다.
- 급정지장치는 작업자가 어느 장소에서나 활용할 수있는위치에 부착되어야한다.
- -로울러에 협착될 위험이 있는 부분에는 가이드롤, 울등이 설치되어야한다.
- -로울러기를 청소하거나 점검시에는 반드시 기계 를정지한후실시한다.♠